BANGALORE DIVISION.

ADVERTISEMENT.

The 5th February 1892.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 20th February 1892, for improving the Government Press Building at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1892.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the Government Press Building at Bangalore"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

IMPROVING THE GOVERNMENT PRESS BUILDING AT BANGALORE.

Abstract.

Items.	Per.	Rate.	Quantity.	Cost.
Earthwork	C. Yd.		2,182	
Stone in chunam	C. Ft.		14,239	
Brick in chunam	Do		16,264	
Archwork	Do		212	
Stone slabs, dressed	Sq. Ft.		397	
Bengal terracing	Sqr.		82·75	
Flat terrace	Do		19·44	
Concrete flooring	Do		73·22	
Teakwood work	C. Ft.		1,992·75	
Large windows, with venetian shutters, glazed, &c., (6 × 7) ..	No.		21	
Small do do (3 × 7) ..	Do		21	
Swing do do (3 × 2) ..	Do		26	
Teakwood pannelled door (3 × 6)	Do		1	
Plastering with chunam	Sqr.		267·73	
Whitewashing	Do		168·16	
Colorwashing	Do		117·72	
Cornice	R. Ft.		14·98	
Opening arches, dismantling and rebuilding, &c. ..	No.		22	
Composition of tar	Sqr.		15·46	
Constructing drains and rain water pipes, &c.	Lump Sum.		L. S.	

R. T. SCALDWELL,
Executive Engineer.